



समग्र शिक्षा केरल
Samagra Shiksha Kerala
സമഗ്ര ശിക്ഷാ കേരളം

സ്റ്റേറ്റ് പ്രോജക്ട് ഡയറക്ടറുടെ കാര്യാലയം
സമഗ്ര ശിക്ഷാ (എസ്.എസ്.കെ.), കേരളം
എസ്.എസ്.എ.ഭവൻ, നന്ദാവനം, തിരുവനന്തപുരം - 695 033
ഫോൺ : 0471 2320826, 2320352. ഫാക്സ് : 2320703.
ഇ-മെയിൽ : ssakerala@gmail.com.

നം. എ4/4104/2024/എസ്.എസ്.കെ

തീയതി: 10/06/2026

കാട്ടേഷൻ നോട്ടീസ്

സമഗ്ര ശിക്ഷാ കേരളം സംസ്ഥാന കാര്യാലയത്തിലെ വിവിധ അറ്റകുറ്റ പണികൾ ചെയ്യുന്നതിനായി അംഗീകൃത ഏജൻസികളിൽ നിന്നും കാട്ടേഷൻ ക്ഷണിച്ചുകൊള്ളുന്നു. പ്രസ്തുത അറ്റകുറ്റപ്പണികളുടെ വിശദാംശങ്ങൾ (എസ്റ്റിമേറ്റ് ഉൾപ്പെടെ) ഇതോടൊപ്പം ഉള്ളടക്കം ചെയ്യുന്നു.

കാട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതിയും സമയവും 15.06.2026 4 മണി

കാട്ടേഷൻ തുറക്കുന്ന തീയതിയും സമയവും 15.06.2026 5 മണി.

വിശ്വസ്തതയോടെ,

സ്റ്റേറ്റ് പ്രോജക്ട് ഡയറക്ടർക്കുമേണ്ടി

SAMAGRA SHIKSHA KERALA

Cost - 1.3559


CIVIL WORK 2026

DSR-2018

MAINTENANCE OF SSK STATE OFFICE BUILDING AND PLUMBING WORKS

DETAILED AND ABSTRACT ESTIMATE

Sl. No	Particulars	No	L	B	H	Qty	Units	Amount	
1	18.48 Providing and placing on terrace (at all floor levels) polyethylene water storage tank :ISI 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.								
	2ND FLOOR					500.00	litre		
		500.00	litre @ rs	10.37	/m2			5186.32	
2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter 12.41.2								
	110 MM PIPE	1	4.00			4.00	M		
							Total		
		4.00	m@Rs	359.11	/m	4.00	M	1436.44	
3	"Dismantling existing 110 mm dia PVC/UPVC SWR pipe including fittings, clamps, cutting pipe, removing from wall/ceiling, disposal of debris and stacking serviceable material within 50 metre lead complete as directed by Engineer-in-Charge."(MR)								
	110 MM PIPE	1	4.00			4.00	M		
							Total		
		4.00	m@Rs	150.00	/m	4.00	M	600.00	
4	Providing and fixing waterproof UV stabilized HDPE tarpaulin sheet of approved quality, minimum 150 GSM (or as specified), over existing roof/terrace for temporary protection against rain leakage, including necessary overlap, stitching wherever required, tying with nylon rope/coir rope, fixing with wooden battens/bamboo supports as required, complete in all respects as directed by Engineer-in-Charge.(MR)								
	The rate includes cost of tarpaulin sheet, ropes, nails, battens, labour, transportation, loading/unloading and all incidental charges complete.								
	ROOF	1	10.00	8.00		80.00	m2		
							Total		
		80.00	m2@Rs	100.00	/m2	80.00	m2	10000.00	
	TOTAL								17222.76
	GST 18%								3100.10
	WWF 1%								172.23
	UNFORSEEN								505.00
	GRAND TOTAL								21000.08
RUPEES TWENTY ONE THOUSAND ONLY									


 25/05/26
ANIL. K.V
 State Project Engineer
 Samagra Shiksha Kerala
 Thiruvananthapuram-695 033